



East Water Storage Tank and Pump Station Construction Update

September 14, 2021

www.fortmyersutilities.com

September 2021 Construction Update

In June 2021, contractors for the City of Fort Myers started construction on the East Water Storage Tank and Pump Station. The project is expected to be completed in November 2022.

Construction activities will include:

General Site

- Complete rock removal from the site
- Maintain the dewatering system

Water Storage Tank

- Continue tank excavation
- Install the test auger cast piles
 - Auger cast piles are a type of drilled foundation in which the pile is drilled to the final depth in one continuous process.
- Begin installation of production piles

For project information contact the City's public information consultant, Cella Molnar & Associates, Inc. at 239-337-1071, visit the "**Contact Us**" page on the project website to sign up for email updates and construction information at www.FortMyersUtilities.com, or email info@FortMyersUtilities.com.